



Carrie Eklund
Central Services Manager
Finance Department

ADDENDUM TO BID

US BUSINESS RT 20 FAP RT 303 (W. STATE ST.) SUNSET AVE. TO KENT CREEK WATER & SEWER MAIN REROUTE PROJECT Bid No: 812-PW-106 ADDENDUM #2

To: All Bidders:

Please make the following changes to the above mentioned bid package.

Discard original and addendum no. 1 "Schedule of Prices" and replace with revised "Schedule of Prices" attached hereto.

All other portions remained unchanged.

A copy of this addendum or a reference thereto must be included with your bid or the bid will not be read or considered.

If you have any questions please contact the Central Services Division at (815) 987-5560.

DATED: September 13, 2012


FINANCE AND PERSONNEL COMMITTEE

Carrie Eklund
Central Services Manager

SCHEDULE OF PRICES

US Bus Rt 20 (W State St) Water and Sewer ReRoute Project

CITY OF ROCKFORD BID OPEN:



Revised 9/12/12

Revised 9/13/12

Item No.	Items	Units	Quantity	Unit Price	Total
1	Ductile Water Main, 8" Class 52	L.F.	3,219		
2	Ductile Water Main, 12" Class 52	L.F.	6		
3	Ductile Water Main, 16" Class 51	L.F.	809		
4	Ductile Water Main, 24" Class 51	L.F.	40		
5	HDPE Water Main 14" (DIPS)	L.F.	267		
6	HDPE Water Main 18" (DIPS)	L.F.	778		
7	Disconnect Water Services	Each	10		
8	Fire Hydrant with 6" Valve & Valve Box	Each	17		
9	Gate Valve and Valve Box, 4"	Each	1		
10	Gate Valve and Valve Box, 6"	Each	2		
11	Gate Valve and Valve Box, 8"	Each	8		
12	Butterfly Valve and Valve Box, 12"	Each	1		
13	Butterfly Valve and Valve Box, 16"	Each	4		
14	Line Stop, 6"	Each	7		
15	Line Stop, 8"	Each	2		
16	Connect To Existing 6" Water Main	Each	9		
17	Connect To Existing 8" Water Main	Each	4		
18	Connect To Existing 12" Water Main	Each	1		
19	Connect To Existing 24" Water Main	Each	2		
20	Water Main Protection (10")	L.F.	40		
21	Water Main Protection (16")	L.F.	60		
22	Copper Service Complete, 0.75"	L.F.	56		
23	Copper Service Complete, 1"	L.F.	636		
24	Copper Service Complete, 1.5"	L.F.	21		
25	Copper Service Complete, 2"	L.F.	34		
West State Street Water and Sewer ReRoute Project		Total Bid	As read		
			As corrected		

SCHEDULE OF PRICES US Bus Rt 20 (W State St) Water and Sewer ReRoute Project CITY OF ROCKFORD BID OPEN:				 Revised 9/12/12 Revised 9/13/12	
Item No.	Items	Units	Quantity	Unit Price	Total
26	Ductile Iron Service Complete, 4"	L.F.	80		
27	Ductile Iron Service Complete, 8"	L.F.	80		
28	Cut and Cap Existing Water Main	Each	6		
29	Cut and Plug Existing Water Main	Each	20		
30	Abandon Existing Valve and Valve Vault	Each	22		
31	Remove Existing Valve and Valve Vault	Each	2		
32	Remove Fire Hydrant Complete	Each	13		
33	Abandon Existing Valve and Valve Box	Each	1		
34	Tree Removal (Over 15 units in Dia.)	IN-DIA	30		
35	Rock Excavation	C.Y.	75		
36	Trench Backfill	C.Y.	2,000		
37	Select Foundation Material	C.Y.	30		
38	Permanent Pavement	S.Y.	2,220		
39	PCC Driveway Pavement, 6"	S.Y.	90		
40	PCC Sidewalk, 4"	S.F.	4,250		
41	ADA Curb Ramp Detectable Warning	S.F.	72		
42	Combination Concrete Curb and Gutter	L.F.	600		
43	Storm Sewer, Type 1, 12"	L.F.	60		
44	Storm Sewer, Type 1, 30"	L.F.	16		
45	Storm Sewer, Type 1, 48"	L.F.	10		
46	Silt Fence	L.F.	2,256		
47	Erosion Control For Inlets	Each	40		
48	Traffic Control and Protection	L.S.	1		
49	Parkway Restoration	L.S.	1		
West State Street Water and Sewer ReRoute Project		Total Bid	As read As corrected		

SCHEDULE OF PRICES

US Bus Rt 20 (W State St) Water and Sewer ReRoute Project

CITY OF ROCKFORD BID OPEN:



Revised 9/12/12

Revised 9/13/12

Item No.	Items	Units	Quantity	Unit Price	Total
50	8" Diameter PVC SDR35 (D3034) Sanitary Sewer	L.F.	524		
51	8" Diameter PVC SDR26 (D2241) Sanitary Sewer	L.F.	480		
52	10" Diameter PVC SDR26 (D2241) Sanitary Sewer	L.F.	118		
53	15" Diameter PVC SDR35 (D3034) Sanitary Sewer	L.F.	30		
54	4' Diameter Sanitary Manhole	Each	5		
55	4' Diameter Sanitary Drop Manhole	Each	2		
56	5' Diameter Sanitary Drop Manhole	Each	1		
57	4' Diameter Private Service Manhole	Each	2		
58	Sanitary Sewer Service Stub	Each	7		
59	Sanitary Sewer Service Reconnection, 4"	Each	24		
60	Sanitary Sewer Service Reconnection, 6"	Each	3		
61	Sanitary Sewer Service Replacement - Private Property	Each	2		
62	Abandon Sanitary Manhole	Each	4		
63	Remove Sanitary Manhole	Each	13		
64	Remove and Replace Sanitary Manhole	Each	10		
65	Temporary Pavement - Light Duty	SY	1,940		
66	Temporary Pavement - Heavy Duty	SY	585		
67	Abandon and Fill Existing Water Main	LF	7,325		
68	Abandon and Fill Existing Sanitary Sewer	Each	4		
15a*	Line Stop, 12"	Each	1		
15b*	Line Stop, 24"	Each	1		
	*Line stops may not be utilized depending on field conditions				
West State Street Water and Sewer ReRoute Project		Total Bid	As read		
			As corrected		