



Carrie Eklund
Central Services Manager
Finance Department

**INVITATION FOR BID
ELM STREET / AVON STREET RESURFACING
414-PW-036**

Bids will be received until **11:00 a.m.**, local time, on **Wednesday, April 23, 2014** at the office of the Central Services Manager, City Hall Building, 425 East State Street, Rockford, Illinois 61104. At that time and place all bids received will be publicly opened and read aloud.

Bids will be accepted until the specified opening time and date. Any bidder attempting to deliver after the opening time and date will be refused.

Each bidder shall submit with his bid the information specified in the bid documents for compliance with the laws of the State of Illinois on Fair Employment Practices and with the City of Rockford's Ordinance on Equal Employment and Business Opportunity. Any bid which fails to include the compliance items properly completed will not be read and will not be considered.

The City of Rockford reserves the right to accept or reject any and all proposals and to waive technicalities.

Dated: April 8, 2014

FINANCE AND PERSONNEL COMMITTEE

Carrie Eklund
Central Services Manager

SCHEDULE OF PRICES

City of Rockford

Project Name: Elm Street/Avon Street Resurfacing - 2014



Item No.	Items	Units	Quantity	Unit Price	Total
1	Earth Excavation	C.Y.	377		
2	Surface Removal, 2.5"	S.Y.	1218		
3	Surface Remvoal, 3"	S.Y.	9735		
4	Bituminous Materials (Prime Coat)	Gal	1587		
5	Aggregate (Prime Coat)	Tons	75		
6	Polymerized Leveling Binder, IL-4.75, N50, 1"	Tons	282		
7	Polymerized Leveling Binder, IL-4.75, N70, 1"	Tons	229		
8	Hot-Mix Asphalt Binder Course, IL-12.5, N70, 6.5"	Tons	925		
9	Hot-Mix Asphalt Surface Course, Mix "C", N50, 1.5"	Tons	110		
10	Hot-Mix Asphalt Surface Course, Mix "C", N50, 2"	Tons	482		
11	Polymerized Hot-Mix Asphalt Surface Course, Mix "C", N70, 2"	Tons	722		
12	Hot-Mix Asphalt, Hand Method	Tons	15		
13	Class B Patch, Type IV, 10"	S.Y.	135		
14	Class C Patch, Type IV, 5"	S.Y.	598		
15	Dowel Bars	Each	4		
16	Transverse Tie Bars	Each	151		
17	Subbase Granular Material, Type B, CA-2, 5"	Tons	101		
18	Aggregate Base Course, Type B, CA-6, 5"	Tons	101		
19	Aggregate Base Repair, 10"	S.Y.	84		
20	Handholes to be Adjusted	Each	2		
21	Sanitary Riser/Valve Boxes to be Adjusted	Each	3		
22	Manholes to be Adjusted	Each	28		
23	Manholes to be Adjusted with New Frame and Lid	Each	17		
24	Manholes to be Reconstructed	Each	1		
Page 1		Sub Total	As read As corrected		

SCHEDULE OF PRICES

City of Rockford

Project Name: Elm Street/Avon Street Resurfacing - 2014



Item No.	Items	Units	Quantity	Unit Price	Total
25	Manholes to be Reconstructed with New Frame and Lid	Each	1		
26	Inlets to be Adjusted	Each	3		
27	Inlets to be Adjusted with New Frame and Grate	Each	4		
28	Inlets to be Reconstructed	Each	1		
29	Inlets to be Reconstructed with New Frame and Grate	Each	4		
30	Inlet Specials to be Repaired	Each	1		
31	Approach Pavement Removal	S.Y.	168		
32	Combination Curb and Gutter Removal	L.F.	2814		
33	Sidewalk Removal	S.F.	10747		
34	P.C.C. Approach Pavement, 6"	S.Y.	10		
35	P.C.C. Approach Pavement, 8"	S.Y.	168		
36	P.C.C. Sidewalk, 4"	S.F.	10477		
37	Detectable Warnings, ADA Ramps	S.F.	320		
38	Combination Concrete Curb and Gutter, Type M-6.18 (Modified)	L.F.	2814		
39	Water Main 8" Ductile Iron Class 52 and Fittings (Polyethylene Wrapped)	L.F.	1667		
40	Gate Valve and Valve Box, 4"	Each	1		
41	Gate Valve and Valve Box, 6"	Each	1		
42	Gate Valve and Valve Box, 8"	Each	12		
43	Fire Hydrant Complete	Each	3		
44	1" Copper Service Complete	Each	3		
45	Connect to Existing 4" Water Main	Each	1		
46	Connect to Existing 6" Water Main	Each	8		
47	Connect to Existing 8" Water Main	Each	1		
48	Connect to Existing 24" Water Main	Each	1		
Page 2		Sub Total		As read	
				As corrected	

