



Carrie Eklund
Central Services Manager
Finance Department

**INVITATION FOR BID
CITY-WIDE STREET REPAIRS GROUP NO.: 2
414-PW-037**

Bids will be received until **11:00 a.m.**, local time, on **Wednesday, April 23, 2014** at the office of the Central Services Manager, City Hall Building, 425 East State Street, Rockford, Illinois 61104. At that time and place all bids received will be publicly opened and read aloud.

Bids will be accepted until the specified opening time and date. Any bidder attempting to deliver after the opening time and date will be refused.

Each bidder shall submit with his bid the information specified in the bid documents for compliance with the laws of the State of Illinois on Fair Employment Practices and with the City of Rockford's Ordinance on Equal Employment and Business Opportunity. Any bid which fails to include the compliance items properly completed will not be read and will not be considered.

The City of Rockford reserves the right to accept or reject any and all proposals and to waive technicalities.

Dated: April 8, 2014

FINANCE AND PERSONNEL COMMITTEE

Carrie Eklund
Central Services Manager

SCHEDULE OF PRICES

City of Rockford

Project Name: City Wide Street Repairs Group No. 2 - 2014



Item No.	Items	Units	Quantity	Unit Price	Total
1	Earth Excavation	C.Y.	50		
2	Hot-Mix Asphalt Surface Removal, 2"	S.Y.	14600		
3	Hot-Mix Asphalt Surface Removal, 2" Alley Pavement	S.Y.	2488		
4	Hot-Mix Asphalt Surface Removal, 2.5"	S.Y.	45908		
5	Concrete Surface Removal, 2.5"	S.Y.	1000		
6	Shaping and Grading Alleyway	S.Y.	2488		
7	Bituminous Materials (Prime Coat)	Gal	6407		
8	Aggregate (Prime Coat)	Tons	316		
9	Polymerized Leveling Binder, IL-4.75, N50, 1"	Tons	2890		
10	Hot-Mix Asphalt Binder Course, IL-9.5, N50, 1.25"	Tons	500		
11	Hot-Mix Asphalt Surface Course, Mix "C", N50, 1.5"	Tons	4332		
12	Hot-Mix Asphalt Surface Course, Mix "C", N50, 2"	Tons	1681		
13	Hot-Mix Asphalt Surface Course, Mix "C", N50, 2" Alley Pavement	Tons	289		
14	Hot-Mix Asphalt, Hand Method	Tons	10		
15	Subbase Granular Material, Type B, CA-2, 5"	Tons	100		
16	Aggregate Base Course, Type B, CA-6, 5"	Tons	100		
17	Aggregate Base Repair, 10"	S.Y.	871		
18	Sanitary Riser/Valve Boxes to be Adjusted	Each	1		
19	Manholes to be Adjusted	Each	35		
20	Manholes to be Adjusted with New Frame and Lid	Each	37		
21	Manholes to be Reconstructed	Each	1		
22	Manholes to be Reconstructed with New Frame and Lid	Each	1		
23	Inlets to be Adjusted	Each	33		
24	Inlets to be Adjusted with New Frame and Grate	Each	13		
Page 1		Sub Total	As read		
			As corrected		

SCHEDULE OF PRICES

City of Rockford

Project Name: City Wide Street Repairs Group No. 2 - 2014



Item No.	Items	Units	Quantity	Unit Price	Total
25	Inlets to be Reconstructed	Each	1		
26	Inlets to be Reconstructed with New Frame and Grate	Each	15		
27	Inlet Specials to be Repaired	Each	1		
28	Approach Pavement Removal	S.Y.	10		
29	Combination Curb and Gutter Removal	L.F.	790		
30	Sidewalk Removal	S.F.	4620		
31	P.C.C. Approach Pavement, 6"	S.Y.	10		
32	P.C.C. Approach Pavement, 8"	S.Y.	10		
33	P.C.C. Sidewalk, 4"	S.F.	4465		
34	Detectable Warnings, ADA Ramps	S.F.	464		
35	Combination Concrete Curb and Gutter, Type M-6.18 (Modified)	L.F.	790		
36	Inlet and Pipe Protection	Each	139		
37	Thermoplastic Pavement Markings, 4"	L.F.	580		
38	Thermoplastic Pavement Markings, 6"	L.F.	215		
39	Thermoplastic Pavement Markings, 24"	L.F.	62		
40	Thermoplastic Pavement Markings, Letters and Symbols	S.F.	16		
41	Parkway Restoration	Lsum	1		
42	Traffic Control and Protection	Lsum	1		

Total Bid	As read
	As corrected