



Carrie Eklund
Central Services Manager
Finance Department

INVITATION FOR BID BROADWAY & AUBURN STREET RESURFACING - 2014 614-PW-060

Bids will be received until **11:00 a.m.**, local time, on **Thursday, June 19, 2014** at the office of the Central Services Manager, City Hall Building, 425 East State Street, Rockford, Illinois 61104. At that time and place all bids received will be publicly opened and read aloud.

Bids will be accepted until the specified opening time and date. Any bidder attempting to deliver after the opening time and date will be refused.

Each bidder shall submit with his bid the information specified in the bid documents for compliance with the laws of the State of Illinois on Fair Employment Practices and with the City of Rockford's Ordinance on Equal Employment and Business Opportunity. Any bid which fails to include the compliance items properly completed will not be read and will not be considered.

The City of Rockford reserves the right to accept or reject any and all proposals and to waive technicalities.

Dated: June 4, 2014

FINANCE AND PERSONNEL COMMITTEE

Carrie Eklund
Central Services Manager

SCHEDULE OF PRICES

City of Rockford

Bid On: Broadway/Auburn Street Resurfacing - 2014



Item No.	Items	Units	Quantity	Unit Price	Total
1	Earth Excavation	C.Y.	105		
2	Surface Removal, 2"	S.Y.	557		
3	Surface Removal, 3"	S.Y.	26186		
4	Hot-Mix Asphalt Surface Removal, 2" Alley Pavement	S.Y.	225		
5	Shaping and Grading Alleyway	S.Y.	225		
6	Bituminous Materials (Prime Coat)	Gal	2675		
7	Aggregate (Prime Coat)	Tons	132		
8	Polymerized Leveling Binder, IL-4.75, N70, 1"	Tons	1606		
9	Polymerized Hot-Mix Asphalt Surface Course, Mix "C", N70, 2"	Tons	3118		
10	Hot-Mix Asphalt Surface Course, Mix "C", N50, 2" Alley Pavement	Tons	26		
11	Hot-Mix Asphalt, Hand Method	Tons	10		
12	Pot Hole Patching	Tons	325		
13	Pavement Fabric	S.Y.	26186		
14	Subbase Granular Material, Type B, CA-2, 5"	Tons	100		
15	Aggregate Base Course, Type B, CA-6, 5"	Tons	100		
16	Aggregate Base Repair, 10"	S.Y.	284		
17	Hand Holes to be Adjusted	Each	5		
18	Sanitary Riser/Valve Boxes to be Adjusted	Each	11		
19	Manholes to be Adjusted	Each	9		
20	Manholes to be Adjusted with New Frame and Lid	Each	55		
21	Manholes to be Reconstructed	Each	1		
22	Manholes to be Reconstructed with New Frame and Lid	Each	2		
23	Inlets to be Adjusted	Each	16		
24	Inlets to be Adjusted with New Frame and Grate	Each	7		
Page 1		Sub Total		As read	
				As corrected	

SCHEDULE OF PRICES

City of Rockford

Bid On: Broadway/Auburn Street Resurfacing - 2014



Item No.	Items	Units	Quantity	Unit Price	Total		
25	Inlets to be Reconstructed	Each	1				
26	Inlets to be Reconstructed with New Frame and Grate	Each	11				
27	Inlet Specials to be Repaired	Each	5				
28	Approach Pavement Removal	S.Y.	466				
29	Combination Curb and Gutter Removal	L.F.	4716				
30	Sidewalk Removal	S.F.	29455				
31	P.C.C. Approach Pavement, 6"	S.Y.	17				
32	P.C.C. Approach Pavement, 8"	S.Y.	414				
33	P.C.C. Sidewalk, 4"	S.F.	34910				
34	Detectable Warnings, ADA Ramps	S.F.	384				
35	Combination Concrete Curb and Gutter, Type M-6.18 (Modified)	L.F.	4716				
36	Detector Loops	L.F.	2000				
37	Inlet and Pipe Protection	Each	65				
38	Thermoplastic Pavement Markings, 4"	L.F.	9732				
39	Thermoplastic Pavement Markings, 6"	L.F.	2529				
40	Thermoplastic Pavement Markings, 12"	L.F.	420				
41	Thermoplastic Pavement Markings, 24"	L.F.	472				
42	Thermoplastic Pavement Markings, Letters and Symbols	S.F.	311				
43	Raised Reflective Pavement Markers Removal	Each	124				
44	Raised Reflective Pavement Markers	Each	211				
45	Parkway Restoration	Lsum	1				
46	Traffic Control and Protection	Lsum	1				
Page 2		Total Bid	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td style="width: 50%; text-align: center;">As read</td> </tr> <tr> <td style="width: 50%; text-align: center;">As corrected</td> </tr> </table>			As read	As corrected
As read							
As corrected							