



Carrie Eklund
Central Services Manager
Finance Department

INVITATION FOR BID WALLIN AVENUE WATER MAIN REPLACEMENT 814-PW-127

THE ENGINEER'S ESTIMATE FOR THIS BID IS \$291,431.50
Please email sue.dewitt@rockfordil.gov with any requests or questions

Bids will be received until **11:00 a.m.**, local time, on **Monday, September 22, 2014** at the office of the Central Services Manager, City Hall Building, 425 East State Street, Rockford, Illinois 61104. At that time and place all bids received will be publicly opened and read aloud.

Bids will be accepted until the specified opening time and date. Any bidder attempting to deliver after the opening time and date will be refused.

Bid documents may be obtained at the office of the Central Services Manager, at City Hall, 425 East State Street, Rockford, IL, 61104. Bids must be enclosed in a sealed envelope and marked with the name of the bid, and the bid number.

Each bidder shall submit with his bid the information specified in the bid documents for compliance with the laws of the State of Illinois on Fair Employment Practices and with the City of Rockford's Ordinance on Equal Employment and Business Opportunity. Any bid which fails to include the compliance items properly completed will not be read and will not be considered. All Contracts for the Construction of Public Works are subject to the Illinois Prevailing Wage Act (820 ILCS 130/1-12).

The City of Rockford reserves the right to accept or reject any and all proposals and to waive technicalities.

Dated: September 8, 2014

FINANCE AND PERSONNEL COMMITTEE

Carrie Eklund
Central Services Manager

SCHEDULE OF PRICES

City of Rockford

Project Name: Wallin Ave. Water Main Improvement



Item No.	Items	Units	Quantity	Unit Price	Total
1	Parkway Restoration	Lsum	1		
2	Inlet and Pipe Protection	Each	5		
3	Bituminous Materials (Prime Coat)	Gal	150		
4	Hot-Mix Asphalt Binder Course, IL-12.5, N-50, 2.5"	Tons	210		
5	Hot-Mix Asphalt Surface Course, Mix "C", N50, 1.5"	Tons	125		
6	Subbase Granular Material Type B, CA-2, 5"	Tons	425		
7	Aggregate Base Course Type B, CA-6, 5"	Tons	425		
8	Class B Patch, Type IV, 10"	S.Y.	110		
9	No. 6 Transverse Tie Bars	Each	25		
10	Dowel Bars, 1.5" Diameter	Each	40		
11	P.C.C. Sidewalk, 4"	S.F.	575		
12	Combination Curb and Gutter, Type M-6.18 Modified	L.F.	195		
13	Combination Curb and Gutter Removal	L.F.	195		
14	Sidewalk Removal	S.F.	575		
15	Pavement Removal	S.Y.	1375		
16	Ductile Iron Water Main Complete, 8"	L.F.	950		
17	Water Main Removal	L.F.	60		
18	Gate Valve and Valve Box Complete, 8"	Each	2		
19	Water Service Complete, 1"	Each	15		
20	Water Service Complete, 2"	Each	1		
21	Fire Hydrant With 6" Valve and Valve Box, Complete	Each	1		
22	Remove Valve Vault and Valve Complete	Each	1		
23	Remove Fire Hydrant Complete	Each	1		
24	Remove Tee Complete	Each	1		
Page 1		Sub Total	As read		
			As corrected		

