



Carrie Eklund
Central Services Manager
Finance Department

**INVITATION TO BID
CITY-WIDE STREET REPAIRS GROUP NO.: 2
(COMMERCIAL AND INDUSTRIAL)
BID NO.: 315-PW-026**

Bids will be received until **11:00 a.m.**, local time, on **Wednesday, March 18, 2015** at the office of the Central Services Manager, City Hall Building, 425 East State Street, Rockford, Illinois 61104. At that time and place all bids received will be publicly opened and read aloud.

Bids will be accepted until the specified opening time and date. Any bidder attempting to deliver after the opening time and date will be refused.

Bid documents may be obtained at the office of the Central Services Manager, at City Hall, 425 East State Street, Rockford, IL, 61104. Bids must be enclosed in a sealed envelope and marked with the name of the bid, and the bid number.

Each bidder shall submit with his bid the information specified in the bid documents for compliance with the laws of the State of Illinois on Fair Employment Practices and with the City of Rockford's Ordinance on Equal Employment and Business Opportunity. Any bid which fails to include the compliance items properly completed will not be read and will not be considered. All Contracts for the Construction of Public Works are subject to the Illinois Prevailing Wage Act (820 ILCS 130/1-12).

The City of Rockford reserves the right to accept or reject any and all proposals and to waive technicalities.

Dated: March 3, 2015

FINANCE AND PERSONNEL COMMITTEE

Carrie Eklund
Central Services Manager

SCHEDULE OF PRICES

City of Rockford

Bid On: City-Wide Street Repairs Group No. 2 - 2015 (Commercial Streets)



Item No.	Items	Units	Quantity	Unit Price	Total
1	Earth Excavation	C.Y.	56		
2	Surface Removal, 2"	S.Y.	35375		
3	Surface Removal, 4.5"	S.Y.	24185		
4	Surface Removal, 2" Edge Milling	S.Y.	6575		
5	Bituminous Materials (Prime Coat)	Gal	7129		
6	Aggregate (Prime Coat)	Tons	348		
7	Hot-Mix Asphalt Binder Course, IL-12.5, N70, 2.5"	Tons	3525		
8	Hot-Mix Asphalt Surface Course, Mix "C", N70, 2"	Tons	8560		
9	Hot-Mix Asphalt, Hand Method	Tons	10		
10	Subbase Granular Material, Type B, CA-2, 5"	Tons	100		
11	Aggregate Base Course, Type B, CA-6, 5"	Tons	100		
12	Aggregate Base Repair, 10"	S.Y.	558		
13	Hand Holes to be Adjusted	Each	1		
14	Sanitary Riser/Valve Boxes to be Adjusted	Each	2		
15	Manholes to be Adjusted	Each	33		
16	Manholes to be Adjusted with New Frame and Lid	Each	16		
17	Manholes to be Reconstructed	Each	1		
18	Manholes to be Reconstructed with New Frame and Lid	Each	1		
19	Inlets to be Adjusted	Each	5		
20	Inlets to be Adjusted with New Frame and Grate	Each	1		
21	Inlets to be Reconstructed	Each	1		
22	Inlets to be Reconstructed with New Frame and Grate	Each	1		
23	Inlet Specials to be Repaired	Each	2		
24	Combination Curb and Gutter Removal	L.F.	464		

Sub Total

As read
As corrected

