



Carrie Eklund
Central Services Manager
Finance Department

**INVITATION TO BID
SPRING BROOK ROAD RESURFACING- 2015
BID NO.: 315-PW-030**

Bids will be received until **11:00 a.m.**, local time, on **Monday, April 6, 2015** at the office of the Central Services Manager, City Hall Building, 425 East State Street, Rockford, Illinois 61104. At that time and place all bids received will be publicly opened and read aloud.

Bids will be accepted until the specified opening time and date. Any bidder attempting to deliver after the opening time and date will be refused.

Bid documents may be obtained at the office of the Central Services Manager, at City Hall, 425 East State Street, Rockford, IL, 61104. Bids must be enclosed in a sealed envelope and marked with the name of the bid, and the bid number.

Each bidder shall submit with his bid the information specified in the bid documents for compliance with the laws of the State of Illinois on Fair Employment Practices and with the City of Rockford's Ordinance on Equal Employment and Business Opportunity. Any bid which fails to include the compliance items properly completed will not be read and will not be considered. All Contracts for the Construction of Public Works are subject to the Illinois Prevailing Wage Act (820 ILCS 130/1-12).

The City of Rockford reserves the right to accept or reject any and all proposals and to waive technicalities.

Dated: March 18, 2015

FINANCE AND PERSONNEL COMMITTEE

Carrie Eklund
Central Services Manager

SCHEDULE OF PRICES

City of Rockford

Bid On: Spring Brook Road Resurfacing - 2015



Item No.	Items	Units	Quantity	Unit Price	Total
1	Earth Excavation	C.Y.	50		
2	Surface Removal, 1"	S.Y.	14500		
3	Surface Removal, 2" (Butt Joints)	S.Y.	2450		
4	Surface Removal, 3"	S.Y.	3900		
5	Bituminous Materials (Prime Coat)	Gal	2735		
6	Aggregate (Prime Coat)	Gal	137		
7	Polymerized Leveling Binder, IL-4.75, N50, 1"	Tons	1200		
8	Polymerized Hot-Mix Asphalt Surface Course, Mix "C", N70, 2"	Tons	3100		
9	Hot-Mix Asphalt, Hand Method	Tons	10		
10	Pavement Reinforcement Fabric	S.Y.	18400		
11	Subbase Granular Material, Type B, CA-2, 5"	Tons	100		
12	Aggregate Base Course, Type B, CA-6, 5"	Tons	100		
13	Aggregate Base Repair, 10"	S.Y.	273		
14	Hand Holes to be Adjusted	Each	2		
15	Manholes to be Adjusted	Each	3		
16	Manholes to be Adjusted with New Frame and Lid	Each	1		
17	Manholes to be Reconstructed with New Frame and Lid	Each	1		
18	Inlet Specials to be Repaired	Each	1		
19	Detector Loops	L.F.	575		
20	Inlet and Pipe Protection	Each	20		
21	Temporary Ditch Checks	Each	20		
22	Thermoplastic Pavement Markings, 4"	L.F.	20575		
23	Thermoplastic Pavement Markings, 6"	L.F.	1055		
24	Thermoplastic Pavement Markings, 12"	L.F.	423		
Page 1		Sub Total	As read As corrected		

