Carrie Eklund
Central Services Manager
Finance Department

INVITATION TO BID
BUCKBEE CREEK AND HARMON PARK REPAIRS
BID NO.: 515-PW-056

Bids will be received until **11:00 a.m.**, local time, on **Monday, June 15, 2015** at the office of the Central Services Manager, City Hall Building, 425 East State Street, Rockford, Illinois 61104. At that time and place all bids received will be publicly opened and read aloud.

Bids will be accepted until the specified opening time and date. Any bidder attempting to deliver after the opening time and date will be refused.

Bid documents may be obtained via email request to: sue.dewitt@rockfordil.gov. or at the office of the Central Services Manager, at City Hall, 425 East State Street, Rockford, IL, 61104. Bids must be enclosed in a sealed envelope and marked with the name of the bid, and the bid number.

Each bidder shall submit with his bid the information specified in the bid documents for compliance with the laws of the State of Illinois on Fair Employment Practices and with the City of Rockford's Ordinance on Equal Employment and Business Opportunity. Any bid which fails to include the compliance items properly completed will not be read and will not be considered. All Contracts for the Construction of Public Works are subject to the Illinois Prevailing Wage Act (820 ILCS 130/1-12).

The City of Rockford reserves the right to accept or reject any and all proposals and to waive technicalities.

Dated: May 20, 2015

FINANCE AND PERSONNEL COMMITTEE

Carrie Eklund
Central Services Manager

SCHEDULE OF PRICES (ALTERNATE)
City of Rockford
Buckbee Creek & Harmon Park Repairs

Item No.	Items	Units	Quantity	Unit Price	Total
1	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	70		
2	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	154		
3	TREE TRUNK PROTECTION	EACH	1		
4	CHANNEL EXCAVATION	CU YD	2,341		
5	POROUS GRANULAR EMBANKMENT	CU YD	3		
6	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	1,289		
7	SEEDING, CLASS 2A	ACRE	0.5775		
8	SEEDING, CLASS 4A	ACRE	0.2664		
9	EROSION CONTROL BLANKET	SQ YD	3,697		
10	TEMPORARY DITCH CHECKS	FOOT	90		
11	PERIMETER EROSION BARRIER	FOOT	1,650		
12	STONE DUMPED RIPRAP, CLASS A5	SQ YD	1,632		
13	FILTER FABRIC	SQ YD	3,840		
14	SLOPE MATTRESS 12"	SQ YD	2,208		
15	REMOVAL OF EXISTING STRUCTURES	EACH	1		
16	STRUCTURE EXCAVATION	CU YD	16		
17	CONCRETE STRUCTURES	CU YD	12		
18	STUD SHEAR CONNECTORS	EACH	106		
19	REINFORCEMENT BARS, EPOXY COATED	POUND	1,090		
20	CHAIN LINK FENCE, 8'	FOOT	160		
21	CHAIN LINK GATES, 8' X 20' DOUBLE	EACH	1		
22	TEMPORARY CONSTRUCTION FENCE	FOOT	575		
23	TEMPORARY ACCESS ROAD (SPECIAL)	SQ YD	503		
24	DEWATERING	LSUM	1		
	Page 1	**Sub Total**	As read		
			As corrected		

SCHEDULE OF PRICES (ALTERNATE)
City of Rockford
Buckbee Creek & Harmon Park Repairs

Item No.	Items	Units	Quantity	Unit Price	Total
25	PIPE CULVERT REMOVAL 15"	FOOT	10		
26	CLEARING AND GRUBBING	LSUM	1		
27	PAVED FLUME REMOVAL	FOOT	33		
28	COFFERDAMS (SPECIAL)	EACH	2		
29	PERMANENT STEEL SHEET PILING	SQ FT	1,790		
30	TEMPORARY CHAIN LINK FENCE	FOOT	286		
31	CHAIN LINK FENCE REMOVAL	FOOT	160		
32	CHAIN LINK GATES REMOVAL	EACH	1		
33	SILT CURTAIN	FOOT	90		
34	CONSTRUCTION STAKING COMPLETE	LSUM	1		
35	FLOW DIVERSION	LSUM	1		
36	PIPE CULVERT OUTLET PROTECTION 15"	LSUM	1		
37	TEMPORARY ACCESS GATE WITH LOCK	EACH	1		
38	TEMPORARY EROSION CONTROL TARP	LSUM	1		
39	TEMPORARY CURB PROTECTION	LSUM	1		
	HARMON PARK				
40	SEEDING, CLASS 2A (HARMON)	ACRE	0.11		
41	EROSION CONTROL BLANKET (HARMON)	SQ YD	505		
42	TEMPORARY DITCH CHECKS (HARMON)	FOOT	120		
43	STONE DUMPED RIPRAP, CLASS A5 (HARMON)	SQ YD	30		
44	FILTER FABRIC (HARMON)	SQ YD	112		
45	SLOPE MATTRESS 12" (HARMON)	SQ YD	112		
46	TEMPORARY CURB PROTECTION (HARMON)	LSUM	1		

Total Bid	As read
	As corrected