



Finance Department
Central Services Division

**INVITATION TO BID
CITY-WIDE STREET REPAIRS GROUP NO.: 2 (RESIDENTIAL)
BID NO.: 316-PW-031**

3/7/16

Bids will be received until **11:00 a.m.**, local time, on **Tuesday, March 22, 2016** at the office of the Central Services Manager, City Hall Building, 425 East State Street, Rockford, Illinois 61104. At that time and place all bids received will be publicly opened and read aloud.

Bids will be accepted until the specified opening time and date. Any bidder attempting to deliver after the opening time and date will be refused.

Bid documents may be obtained via email request to: sue.dewitt@rockfordil.gov. or at the office of the Central Services Manager, at City Hall, 425 East State Street, Rockford, IL, 61104. Bids must be enclosed in a sealed envelope and marked with the name of the bid, and the bid number.

Each bidder shall submit with his bid the information specified in the bid documents for compliance with the laws of the State of Illinois on Fair Employment Practices and with the City of Rockford's Ordinance on Equal Employment and Business Opportunity. Any bid which fails to include the compliance items properly completed will not be read and will not be considered. All Contracts for the Construction of Public Works are subject to the Illinois Prevailing Wage Act (820 ILCS 130/1-12).

The City of Rockford reserves the right to accept or reject any and all proposals and to waive technicalities.

SCHEDULE OF PRICES

City of Rockford

Bid On: City-Wide Street Repairs Group No. 2 - 2016 (Residential)



Item No.	Items	Units	Quantity	Unit Price	Total
1	Earth Excavation	C.Y.	77		
2	Surface Removal, 2"	S.Y.	56500		
3	Bituminous Materials (Prime Coat)	Gal	5152		
4	Aggregate (Prime Coat)	Tons	258		
5	Hot-Mix Asphalt Binder Course, IL-9.5, N50, 1.25"	Tons	500		
6	Hot-Mix Asphalt Surface Course, Mix "C", N50, 2"	Tons	6865		
7	Hot-Mix Asphalt, Hand Method	Tons	10		
8	Subbase Granular Material, Type B, CA-2, 5"	Tons	100		
9	Aggregate Base Course, Type B, CA-6, 5"	Tons	100		
10	Aggregate Base Repair, 10"	S.Y.	512		
11	Sanitary Riser/Valve Boxes to be Adjusted	Each	7		
12	Manholes to be Adjusted	Each	1		
13	Manholes to be Adjusted with New Frame and Lid	Each	86		
14	Manholes to be Reconstructed	Each	1		
15	Manholes to be Reconstructed with New Frame and Lid	Each	1		
16	Inlets to be Adjusted	Each	21		
17	Inlets to be Adjusted with New Frame and Grate	Each	12		
18	Inlets to be Reconstructed	Each	1		
19	Inlets to be Reconstructed with New Frame and Grate	Each	27		
20	Inlet Specials to be Repaired	Each	1		
21	Approach Pavement Removal	S.Y.	649		
22	Combination Curb and Gutter Removal	L.F.	3525		
23	Sidewalk Removal	S.F.	32295		
24	P.C.C. Approach Pavement, 6"	S.Y.	495		
Page 1		Sub Total		As read	
				As corrected	

