



Finance Department
Central Services Division

**INVITATION TO BID
BRIDGE AND ROADWAY REMOVAL AND REPAIRS
BID NO.: 416-PW-043**

4/1/16

Bids will be received until **11:00 a.m.**, local time, on **Monday, April 18, 2016** at the office of the Central Services Manager, City Hall Building, 425 East State Street, Rockford, Illinois 61104. At that time and place all bids received will be publicly opened and read aloud.

Bids will be accepted until the specified opening time and date. Any bidder attempting to deliver after the opening time and date will be refused.

Bid documents may be obtained via email request to: sue.dewitt@rockfordil.gov. or at the office of the Central Services Manager, at City Hall, 425 East State Street, Rockford, IL, 61104. Bids must be enclosed in a sealed envelope and marked with the name of the bid, and the bid number.

Each bidder shall submit with his bid the information specified in the bid documents for compliance with the laws of the State of Illinois on Fair Employment Practices and with the City of Rockford's Ordinance on Equal Employment and Business Opportunity. Any bid which fails to include the compliance items properly completed will not be read and will not be considered. All Contracts for the Construction of Public Works are subject to the Illinois Prevailing Wage Act (820 ILCS 130/1-12).

The City of Rockford reserves the right to accept or reject any and all proposals and to waive technicalities.

SCHEDULE OF PRICES

City of Rockford

Project Name: Bridge and Roadway Removal and Repairs-2016



Item No.	Items	Units	Quantity	Unit Price	Total
1	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	30		
2	TREE TRUNK PROTECTION	EACH	5		
3	TREE ROOT PRUNING	EACH	1		
4	EARTH EXCAVATION	CU YD	232		
5	FURNISHED EXCAVATION	CU YD	986		
6	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	5415		
7	SEEDING, CLASS 2A	ACRE	1		
8	NITROGEN FERTILIZER NUTRIENT	POUND	102		
9	PHOSPHORUS FERTILIZER NUTRIENT	POUND	102		
10	POTASSIUM FERTILIZER NUTRIENT	POUND	102		
11	EROSION CONTROL BLANKET	SQ YD	5411		
12	TEMPORARY EROSION CONTROL SEEDING	POUND	112		
13	PERIMETER EROSION BARRIER	FOOT	2291		
14	INLET FILTERS	EACH	8		
15	AGGREGATE SUBGRADE IMPROVEMENT 12"	SQ YD	258		
16	BITUMINOUS MATERIALS (TACK COAT)	POUND	595		
17	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	101		
18	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	19		
19	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	12		
20	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1289		
21	DETECTABLE WARNINGS	SQ FT	60		
22	PAVEMENT REMOVAL	SQ YD	1415		
23	DRIVEWAY PAVEMENT REMOVAL	SQ YD	50		
24	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1779		
Page 1		Sub Total	As read		
			As corrected		

SCHEDULE OF PRICES

City of Rockford

Project Name: Bridge and Roadway Removal and Repairs-2016



Item No.	Items	Units	Quantity	Unit Price	Total
25	SIDEWALK REMOVAL	SQ FT	4990		
26	MEDIAN REMOVAL	SQ FT	537		
27	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		
28	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1		
29	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1		
30	CONCRETE REMOVAL	CU YD	18.2		
31	PROTECTIVE SHIELD	SQ YD	254		
32	CONCRETE STRUCTURES	CU YD	4.6		
33	CONCRETE SUPERSTRUCTURE	CU YD	18.2		
34	REINFORCEMENT BARS, EPOXY COATED	POUND	4420		
35	REINFORCEMENT BARS	POUND	600		
36	BAR SPLICERS	EACH	24		
37	STORM SEWER REMOVAL 12"	FOOT	4		
38	INLETS, TYPE A, TYPE 11 FRAME AND GRATE	EACH	1		
39	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 8 GRATE	EACH	1		
40	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	3		
41	INLETS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1		
42	REMOVING INLETS	EACH	9		
43	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	886		
44	GUARDRAIL REMOVAL	FOOT	209		
45	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3		
46	MOBILIZATION	LSUM	1		
47	SHORT TERM PAVEMENT MARKING	FOOT	1712		
48	SHORT TERM PAVEMENT MARKING REMOVAL	SQ FT	571		
Page 2		Sub Total		As read	
				As corrected	

SCHEDULE OF PRICES

City of Rockford

Project Name: Bridge and Roadway Removal and Repairs-2016



Item No.	Items	Units	Quantity	Unit Price	Total
49	TEMPORARY CONCRETE BARRIER	FOOT	437.5		
50	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	387.5		
51	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	1		
52	SIGN PANEL - TYPE 1	SQ FT	50		
53	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	15		
54	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	1		
55	RELOCATE SIGN PANEL - TYPE 1	SQ FT	4		
56	TELESCOPING STEEL SIGN SUPPORT	FOOT	113		
57	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	37		
58	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1062		
59	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	15		
60	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	210		
61	PAVEMENT MARKING REMOVAL	SQ FT	215		
62	REMOVE TEMPORARY CONCRETE BARRIER	FOOT	418		
63	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	1		
64	PAVEMENT REMOVAL (SPECIAL)	SQ YD	2333		
65	FRAMES AND LIDS, SPECIAL	EACH	2		
66	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	LSUM	1		
67	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES	LSUM	1		
68	CLEANING AND PAINTING STEEL BRIDGE NO. 1	LSUM	1		
69	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	135		
70	CONSTRUCTION LAYOUT	LSUM	1		
71	SILICONE JOINT SEALER, 2.5"	FOOT	140		
72	POLYMER CONCRETE	CU FT	9		
Page 3		Sub Total	As read		
			As corrected		

