



Finance Department
Central Services Division

**INVITATION TO BID
WEST STATE STREET SIDEWALK REPAIRS
(ROCK RIVER TO WYMAN STREET)
BID NO.: 316-PW-042**

4/15/16

Bids will be received until **11:00 a.m.**, local time, on **Monday, May 2, 2016** at the office of the Central Services Manager, City Hall Building, 425 East State Street, Rockford, Illinois 61104. At that time and place all bids received will be publicly opened and read aloud.

Bids will be accepted until the specified opening time and date. Any bidder attempting to deliver after the opening time and date will be refused.

Bid documents may be obtained via email request to: sue.dewitt@rockfordil.gov. or at the office of the Central Services Manager, at City Hall, 425 East State Street, Rockford, IL, 61104. Bids must be enclosed in a sealed envelope and marked with the name of the bid, and the bid number.

Each bidder shall submit with his bid the information specified in the bid documents for compliance with the laws of the State of Illinois on Fair Employment Practices and with the City of Rockford's Ordinance on Equal Employment and Business Opportunity. Any bid which fails to include the compliance items properly completed will not be read and will not be considered. All Contracts for the Construction of Public Works are subject to the Illinois Prevailing Wage Act (820 ILCS 130/1-12).

The City of Rockford reserves the right to accept or reject any and all proposals and to waive technicalities.

SCHEDULE OF PRICES

City of Rockford

West State Street Sidewalk Repairs (Rock River to Wyman Street)



Item No.	Items	Units	Quantity	Unit Price	Total
1	INLET AND PIPE PROTECTION	EACH	1		
2	PORTLAND CEMENT CONCRETE SIDEWALK, 5-INCH	SQ FT	3270		
3	DETECTABLE WARNINGS	SQ FT	16		
4	COMBINATION CURB AND GUTTER REMOVAL	L.F.	141		
5	SIDEWALK REMOVAL	SQ FT	3889		
6	MEDIAN REMOVAL	SQ FT	71		
7	MANHOLES TO BE ADJUSTED	EACH	1		
8	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.18 (MODIFIED)	L.F.	141		
9	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2"	L.F.	308		
10	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 3"	L.F.	92		
11	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 4"	L.F.	147		
12	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1		
13	HANDHOLE, COMPOSITE CONCRETE	EACH	1		
14	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE), 1/C NO.10	L.F.	1048		
15	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE), 1/C NO.6	L.F.	1156		
16	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE), 1/C NO.2	L.F.	1017		
17	LIGHT POLE FOUNDATION, 24" DIAMETER	L.F.	31		
18	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	2		
19	REMOVAL OF POLE FOUNDATION	EACH	2		
20	PAINT NEW TRAFFIC SIGNAL POST	EACH	1		
21	PAINT NEW COMBINATION MAST ARM AND POLE, UNDER 40-FOOT	EACH	1		
22	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C	L.F.	668		
23	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	L.F.	852		
24	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	L.F.	337		
Page 1		Sub Total	As read		
			As corrected		

SCHEDULE OF PRICES

City of Rockford

West State Street Sidewalk Repairs (Rock River to Wyman Street)



Item No.	Items	Units	Quantity	Unit Price	Total
25	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	L.F.	274		
26	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 14 FT	EACH	1		
27	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE, 26 FT	EACH	1		
28	DRILL EXISTING HANDHOLE	EACH	1		
29	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	1		
30	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	2		
31	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1		
32	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2		
33	TRAFFIC SIGNAL BACKPLATE	EACH	2		
34	REMOVE EXISTING HANDHOLE	EACH	4		
35	REMOVE EXISTING HEAVY-DUTY HANDHOLE	EACH	2		
36	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1		
37	TUBULAR TRAFFIC SIGN POST	EACH	1		
38	TRAFFIC CONTROL AND PROTECTION, SPECIAL	L. SUM	1		
39	HANDHOLE TO BE ADJUSTED	EACH	1		
40	LIGHT POLE, SPECIAL (F1)	EACH	4		
41	LIGHT POLE, SPECIAL (F2)	EACH	1		
42	LUMINAIRE, LED, HORIZONTAL MOUNT, 66 WATT	EACH	4		
43	LUMINAIRE, LED, HORIZONTAL MOUNT, 125 WATT	EACH	1		
44	STAMPED, COLORED PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	523		
45	VAULT CEILING SLAB REPAIR (PARTIAL)	SQ FT	100		
46	VAULT WATERPROOFING	SQ FT	120		
47	REMOVING AND RESETTING STREET SIGNS	EACH	3		
48	TREE VAULT WITH FRAME AND GRATE	EACH	4		
Page 2		Sub Total		As read	
				As corrected	

